



DATE: June 15, 2001

SUBJECT: Transportation of Portable Top Drive Support Unit (TDSU) Buildings

SERIAL NUMBERS: All Portable TDSU's

DISCUSSION: The TDSU building contains many sensitive and fragile electronic systems and components. These components may be susceptible to vibrations and shock.

RECOMMENDATION: When loading and off-loading the TDSU building, extreme caution should be given, not to drop or "jerk" the building. When transporting TDSU buildings by truck, only 'Air-Ride' trailers should be used. Failure to use the proper type of trailer may lead to premature failure of components and downtime.

INFORMATION:

For further information contact:

Field Operations Manager
Canrig Drilling Technology Ltd.
14703 FM 1488
Magnolia, Texas 77354
Phone: 281.259.8887
Fax: 281.259.8158

This page intentionally left blank